

	Washington State Department of Transportation I-405, Brickyard to SR 527 Improvement Project Contract No. 009727	Doc Type: TRAN
		REV#: 0
		SPEC SECTION: 2.6
		DATE: 06/18/2026
		CRE #: BY-CRE-05734


To: Washington State Dept. of Transportation 777 108 th Avenue NE Suite 800 Bellevue, WA 98004	From: Skanska USA Civil West 1995 Agua Mansa Road Riverside, CA 92509
Submittal: BY-CRE-05734_009727_TRAN_16.01_NDC 145 Segment 2 Geotech Addendum 5 RFC	

SKA REFERENCE DOCUMENTS
--

Subcontractor/Supplier: AECOM
SKA Title and Description: NDC 145 Segment 2 Geotech Addendum 5 RFC Due Date: N/A

ADDITIONAL REMARKS

Empty box for additional remarks

Approved by  _____
Patrick Prendergast, Vice President - Operations

Geotechnical Design Services

Project Segment 2 – Addendum 5
Associated with NDC 145
I-405, Brickyard to SR 527 Improvement Project
King and Snohomish Counties, Washington
Contract Number: 009727

for
I-405/Brickyard to SR 527 Design Build Team

June 8, 2026

17425 NE Union Hill Road, Suite 250
Redmond, Washington 98052
425.861.6000



Geotechnical Design Services

Project Segment 2 – Addendum 5
Associated with NDC 145
I-405, Brickyard to SR 527 Improvement Project
King and Snohomish Counties, Washington
Contract Number: 009727


File No. 0180-423-04
June 8, 2026

Prepared for:

I-405/Brickyard to SR 527 Design Build Team
c/o AECOM Technical Services, Inc.
7595 East Technology Way, Suite 200
Denver, Colorado 80237

Prepared by:

GeoEngineers, Inc.
17425 NE Union Hill Road, Suite 250
Redmond, Washington 98052
425.861.6000



David Cantor, Ph.D.
Staff Geotechnical Scientist

Piradeepan Uthayakumar, EIT
Staff Geotechnical Engineer

Kirsten R. d'Amelio, PE
Geotechnical Engineer

Senior Geotechnical Scientist

Timothy D. Bailey, PE
Associate Geotechnical Engineer

Benjamin M. Upsall, PE
Principal Geotechnical Engineer

PU:TB:BMU

Disclaimer: Any electronic form, facsimile, or hard copy of the original document (email, text, table, and/or figure), if provided, and any attachments are only a copy of the original document. The original document is stored by GeoEngineers, Inc. and will serve as the official document of record.

Table of Contents

Table of Contents	i
0.0 Revision Log.....	4
1.0 Introduction	4
2.0 Description of Design Elements and Selected Critical Design Sections.....	6
2.1 NB I-405 to SR 522 Ramp Bridge, NB I-405 Mainline Bridge, and CIP Walls 23.60R-A and 23.60R-B	6
2.2 Retaining Walls	7
2.2.3 EPS Lightweight Fill Wall 23.72R, Wall 23.73R, Mainline Bridge North Embankment, and DA Bus Ramp.....	7
4.0 Geotechnical Explorations, In-Situ and Laboratory Testing, and Groundwater Data.....	8
4.1 Geotechnical Explorations.....	8
4.1.1 Post-Award and Supplemental Post-Award Geotechnical Explorations	8
4.1.3 Geotechnical Explorations Selected for Design of Segment 2 Design Elements.....	9
4.2 In-Situ and Laboratory Testing	12
4.2.1 Post-Award and Supplemental Post-Award In-Situ and Laboratory Testing.....	12
6.0 Design Soil Properties and Design Groundwater Elevations	12
6.1 Design Soil Properties for Existing Soils	12
6.2 Design Soil Properties for Proposed Fill and Aggregate	22
6.2.1 Proposed Granular Fill and Aggregate	22
6.2.2 Proposed EPS Lightweight Fill	22
6.4 Lateral Migration of the Sammamish River and Scour at Mainline Bridge Pier 4	23
7.0 Conclusions and Recommendations	25
7.1 Seismic Hazard Analysis.....	25
7.1.2 Liquefaction Potential	25
7.1.3 Liquefaction-Induced Weakening Instability – Lateral Spreading and Flow Failure ...	27
7.2 Lateral Earth Pressures.....	28
7.2.1 General.....	28
7.2.2 NB I-405 to SR 522 Ramp Bridge and NB I-405 Mainline Bridge.....	29
7.3 Lateral Loading – Drilled Shaft Foundations	30
7.4 Axial Loading – Drilled Shaft Foundations	30
7.4.1 Axial Resistance.....	30
7.4.2 Post-Seismic Liquefaction-Induced Downdrag.....	32
7.4.3 Drilled Shaft Group Settlement and Tip Grouting.....	32
7.5 Bearing Resistance	35
7.6 Coefficient of Sliding Friction	37
7.7 Settlement.....	39
7.7.3 Walls 23.72R, 23.73R, and 23.74R; Mainline Bridge North Embankment; and DA Bus Ramp	39